





CSS UNDERGROUND UTILITIES DATABASE

The Construction Support Services Underground Utilities database has over 4500 items of work covering all phases of utility construction including Water, Sanitary Sewer, Storm Sewer, Manholes, Gas Service and Misc Concrete work.

This database is complete with labor, material and sub contract unit pricing which can be modified by the end user with their specific historical data.

Database Specifications:

Over 4500 Items

Over 186 Phases

Over 230 Formulas


Over 60 Material classes


Over 30 Assemblies


Database Group Phases:

General Conditions	1.000
Fees & Permits	1.700
Mobilization	1.750
Erosion Control	1.900
Site Demolition	2.000
Site Excavation	2.100
Paving	2.200
Water Main	2.300
Domestic Water	2.400
Sanitary Sewer	2.500
Storm Drainage	2.600
Manholes	2.650
Gas Service	2.700
French Drains	2.720
Fence & Guardrails	2.800
Landscape & Irrigation	2.900
Misc. Sitework	2.955
Concrete	3.000

Dalabase Assemblies.	
General Conditions	1 Assembly
Mobilization	1 Assembly
Demo Paving	2 Assemblies
Erosion Control	3 Assemblies
Paving & Walks	7 Assemblies
Water Main	3 Assemblies
Sanitary Sewer	1 Assembly
Storm Sewer	1 Assembly
Manholes	1 Assembly
Gas Service	1 Assembly
Formed Concrete	6 Assemblies







Construction Support Services 959 Lake Harbour Dr. #702, Ridgeland, Ms. 39157 817-504-5812

Phase	Description	Takeoff Quantity	Labor Productivity	Labor Cost/Unit	Labor Quantity	Labor Amount	Material Price	Material Amount	Sub Price	Sub Amount	Total Amount
	WATER MAIN										
2.312	PIPE - PVC										
	c900 DR18 150# PVC Pipe 6"	500.00 lf	20	,12	-	-	5.98 /lf	2,990	¥8	20	2,990
2.314	PVC FITTINGS	151703003000					1,000,000	1000000			1000000
	CI 200 PVC 6" 90 Deg Ell	2.00 each	0.500 ch/eac	51.98 /ea	1.00 ch	104	54.67 /eac	109	10		213
	CI 200 PVC 6" 45 Deg Ell	1.00 each	0.500 ch/eac	51.98 /ea	0.50 ch	52	51.70 /eac	52			104
2.345	WATER MAIN BEDDING										
	Excavation	518.52 cy	0.033 ch/cy	3.43 /cy	17.11 ch	1,779	-	2	23		1,779
	Crush Limestone 3/4"	97.55 tn	0.033 ch/tn	3.43 <i>f</i> tn	3.22 ch	335	20.76 /tn	2,025	28	20	2,360
	Crush Limestone 3/4"	97.55 tn	0.033 ch/tn	3.43 /tn	3.22 ch	335	20.76 /tn	2,025	20	2	2,360
	Haul Off Spoil	195.09 cy	0.100 ch/cy	10.40 /cy	19.51 ch	2,028		-	9.00 /cy	1,756	3,784
2.393	WATER MAIN LABOR										
	Water Main Labor Crew	2.50 dy		623.70 /dy	2.50 dy	1,559	-	8	•		1,559
	STORM DRAINAGE										
2.601	STORM DRAINAGE BEDDING										
	Excavation	444.44 cy	0.033 ch/cy	3.43 /cy	14.67 ch	1,525			-53		1,525
	Crush Limestone 3/4"	30.37 tn	0.033 ch/tn	3.43 <i>f</i> tn	1.00 ch	104	20.76 /tn	631	-83		735
	Crush Limestone 3/4"	30.37 tn	0.033 ch/tn	3.43 /tn	1.00 ch	104	20.76 /tn	631	- 3		735
	Sand Cushion	100.00 cy	0.033 ch/cy	3.43 /cy	3.30 ch	343	14.53 /cy	1,453	<u> </u>	20	1,796
	Haul Off Spoil	160.73 cy	0.250 ch/cy	25.99 /cy	40.18 ch	4,177		-	9.00 /cy	1,447	5,624
2.602	CL III T&G RCP										
	24" CL III Reinf.Conc.Pipe	250.00 lf			-		27.04 Af	6,760	**		6,760
2.608	RCP FITTINGS										
	24" R.C.P. 45 Deg.Bend	2.00 ea	3.000 ch/ea	311.85 /ea	6.00 ch	624	461.04 /ea	922	8	20	1,546
2.635	STORM SEWER LABOR										
	5 Man Pipe Crew	250.00 lf	18.750 If / ch	5.54 Af	13.33 ch	1,386			7/0	5	1,386